

Wiring / current status



Wiring work / inventory per fitting terminal point

of the lines already laid on site according to our specifications by CONTI+ electricians_x000D_ on CONTI+ fittings and the associated control unit.

- Inspection of the object with specialist tradesman
- Inspection and recording of all CONTI+ products to be wired
- Establishing the electrical connections for the electrical lines already installed on site in accordance with the CONTI+ topology as well as ready-mounted fittings and control units (CONTI+ scope of delivery)
- Create as-built drawings for the required system parameterization of the CNX water management system based on existing building plans.
- Functional test of the fittings (depending on the progress of construction)

Calculation of service is per line terminal point in valve or control unit. plus travel - costs correspond to the cost rates for customer service work.

Plus travel - costs correspond to the cost rates for customer service work.

Note:

The electrical wiring may only be carried out by a qualified electrician in accordance with DIN VDE 105-100 be carried out.