

CNX Commissioning



CNX commissioning up to 150 valves

Building-specific parameterization of up to 150 fittings based on the existing as-built plan according to CONTI+ standard, taking into account the following customer specifications (change of standard factory setting):

- Grouping thermal rinsing, cold water rinsing and hygienic rinsing
- Water running times shower mode, hygienic flushing, thermal flushing
- Operating times, trigger times, trigger functions for hygienic flushing, thermal flushing
- Software installation and system check on ready-to-operate system

This includes settings of individual groups. Customer-specific settings of individual fittings are billed separately.

Plus travel - costs correspond to the cost rates for customer service work.

Attributes:

[inbetriebnahme]: Up to 150 faucets,